

# Problem Statement and Motivation

## Real-time scenario:

You have joined as a DevOps engineer in XYZ Pvt. Ltd. It is a platform where individuals can create their profile and start blogging on various topics. The application is ready to be hosted on a server.

You are tasked with implementing an Ansible script to deploy this application on a remote Nginx server.

## Step1. Creating inventory / host file

localhost

[node1]

192.168.0.170 # node1 centos

[node2]

192.168.0.171 # node2 kali

## Step2. Write the playbook

Main.yml

---

- name: Deploy application on Nginx server

hosts: node2

become: yes

tasks:

- name: Install Nginx

apt:

name: nginx

state: present

#update\_cache: yes

- name: Start and enable Nginx service

systemd:

name: nginx

state: started

enabled: yes

- name: copy the web file into the hosts

copy:

```

    src: ./index.html
    dest: /var/www/html/
- name: configure nginx
  template:
    src: ./nginx_config.j2
    dest: /etc/nginx/sites-available/default
- name: test nginx configuration
  command: nginx -t
  register: nginx_test
- name: display the output of nxgin test
  debug:
    var: nginx_test
- name: reload nginx
  systemd:
    name: nginx
    state: reloaded

```

### Step3. Creating J2 (jinja2 template)

#### nginx\_config.j2

```

server {
    listen 80;

    server_name node2; # 192.168.0.171

    location / {
        root /var/www/html;

        index index.html index.htm;
    }
}

```

## Step4. Web application sample

### Index.html

```
<!DOCTYPE html>
```

```
<html>
```

```
<head>
```

```
  <meta charset="UTF-8" />
```

```
  <title>Ansible Lab</title>
```

```
</head>
```

```
<body>
```

```
  <h1> This is the demo of using Ansible to install nginx <br>and depolying the web application.
```

```
</h1>
```


```
<h2>This is the first project from Simplilearn about CM - Ansible</h2>
```

```
</body>
```

```
</html>
```

## Step5. Run playbook / Ansible commands

```
ansible-playbook -i hosts -b -k -K main.yml
```



```
main.yml Ansible_Terraform\main.yml
2 - name: Deploy application on Nginx server
5 tasks:

TASK [Gathering Facts] *****
[WARNING]: Platform linux on host 192.168.0.171 is using the discovered Python interpreter at /usr/bin/python, but future installation of another Python
interpreter could change the meaning of that path. See https://docs.ansible.com/ansible/2.10/reference_appendices/interpreter_discovery.html for more information.
ok: [192.168.0.171]

TASK [Install Nginx] *****
ok: [192.168.0.171]

TASK [Start and enable Nginx service] *****
ok: [192.168.0.171]

TASK [copy the web file into the hosts] *****
ok: [192.168.0.171]

TASK [configure nginx] *****
ok: [192.168.0.171]

TASK [test nginx configuration] *****
changed: [192.168.0.171]

TASK [display the output of nginx test] *****
ok: [192.168.0.171] => {
  "nginx_test": {
    "changed": true,
    "cmd": [
      "nginx",
      "-t"
    ],
    "delta": "0:00:00.000311",
    "end": "2025-01-26 03:18:14.721979",
    "failed": false,
    "rc": 0,
    "start": "2025-01-26 03:18:14.713048",
    "stderr": "nginx: the configuration file /etc/nginx/nginx.conf is not readable (2)",
    "stderr_lines": [
      "nginx: the configuration file /etc/nginx/nginx.conf is not readable (2)",
      "nginx: configuration file /etc/nginx/nginx.conf not readable (2)"
    ],
    "stdout": "",
    "stdout_lines": []
  }
}
```

```
ok: [192.168.0.171] => {
  "nginx_test": {
    "changed": true,
    "cmd": [
      "nginx",
      "-t"
    ],
    "delta": "0:00:00.000311",
    "end": "2025-01-26 03:18:14.721979",
    "failed": false,
    "rc": 0,
    "start": "2025-01-26 03:18:14.713048",
    "stderr": "nginx: the configuration file /etc/nginx/nginx.conf is not readable (2)",
    "stderr_lines": [
      "nginx: the configuration file /etc/nginx/nginx.conf is not readable (2)",
      "nginx: configuration file /etc/nginx/nginx.conf not readable (2)"
    ],
    "stdout": "",
    "stdout_lines": []
  }
}

TASK [reload nginx] *****
changed: [192.168.0.171]

PLAY RECAP *****
192.168.0.171 : ok=8 changed=2
```

shalon@DKPC:/mnt/c/Users/dikka/OneDrive/Desktop/Devops Engineer/Ansible\_Terraform/Ansible\_Terraform

kali [Em execução] - Oracle VM VirtualBox

Ficheiro Máquina Ver Entrada Dispositivos Ajuda

Ansible Lab

192.168.0.171

This is the demo of using Ansible to install nginx and depolyng the web application.

This is the first project from Simplilearn about CM - Ansible